

PG LIFELINK Laser and X-ray Isolated Power Panels are designed for quick and simple field installation. The back box is shipped first, during the "roughing in" phase, allowing the contractor to mount the box as the walls are being erected. The back box must be located in accordance with NEC requirements. The subpanel and front trim are shipped during the "final" construction phase. The transformer, LIM, circuit breakers, and all other components are pre-assembled on the subpanel and wired at the factory. The contractor needs only to mount the subpanel inside the back box and connect the primary feeder, branch circuits and signal conductors. Ample space is provided in the panel for field wiring.

Field checkout, equipment certification and staff orientation by a **PG LIFELINK** factory representative is available.